

Smart Meter Installation Procedure

Document ID: SM-IN-002

Document Type: Procedure

Department: Field Operations

Version: 1.0

Knowledge Base: Smart Meter AI Assistant — Synthetic Business Document

Pre-installation

Verify the service, meter identity, approved meter model, work order, installation location, safety conditions, and required tools before installation.

Physical installation

Install the meter according to the approved wiring diagram and safety procedure. Verify terminals, phase identification, neutral connection, seals, and physical condition.

Electrical checks

After energization, check voltage, current, phase condition, display, clock, and basic registers. Abnormal readings require investigation.

Communication setup

Verify communication module status, SIM status, APN configuration, network registration, and signal information where available.

Commissioning

Commission the meter using the approved workflow and map the correct meter identity to the HES.

Validation

Validate meter identity, communication, time synchronization, initial reads, and downstream registration after commissioning.

Operational note

This is synthetic content created for local RAG development, testing, interview demonstration, and GitHub publication. It is not a confidential utility procedure or contractual document.